

## General Conditions For All Ecosystems:

To use in the field as reference to possible violations of the permit and facilitate timely reporting of possible violations including pictures, videos with coordinates/location. For any possible frack out call the DNR Spills Line: 1 800-405-0016. For any other issue contact: Kyle McLaughlin/Wisconsin Department of Natural Resources/Phone: (715)-360-6148 [Kyle.McLaughlin@VVisconsin.gov](mailto:Kyle.McLaughlin@VVisconsin.gov) These details to reporting any potential violation are on the website: <https://watchtine5.com/report-violations/>

### General Conditions:

- Flagging/stakes must delineate the boundaries of the construction area
- Maintain adequate tarps, silk fencing, sandbags, straw cover/bales to prevent construction fluids from entering the wetlands/waterways from workspace and mats.
- Construction equipment used for the Project shall be the right size to do the job, and be moved without causing unreasonable harm to topsoils, vegetative cover, fish and wildlife habitat
- Temporary access roads necessary to inspect and repair erosion and sediment control practices shall remain in place until final work on site is completed.
- Springs may encountered in the ROW that cannot be avoided by construction. Monitors should document such sitings for future use in verifying timely reporting to DNR.
- Any spill of fossil fuels ( diesel/lubricants, etc.) in a workspace must be reported to the DNR Spills Line. Spills of hazardous materials affecting wetlands and waterways must be reported; and spills that pose a threat to human health must be cleaned up.
- Erosion control devices (tarps, silk fencing, sandbags, straw cover/bales) must be in-place and effective during every phase of the project and defective ones must be repaired/replaced immediately.

Invasive Species Conditions- (Eg common to the watershed: Bishop's goutweed, Garlic mustard, Japanese barberry, Hemp nettle, Common buckthorn, purple loosestrife)

- Inspections to be done on all tools, vehicles, mats and equipment entering and leaving the Project ensure no vegetation, soil or debris are present. If present, the tools, vehicles, and equipment must be removed and contained, preventing spread of invasives.
- Minimize/stabilize soil disturbance and manage
- Moving timber products to or from sites shall comply with Department's Forestry Division restrictions -within 25 miles

General Endangered Species : <https://dnr.wisconsin.gov/topic/EndangeredResources/ETList>

- (Eg. Wolves, eagles, braun holly fern, wood turtle, pugnose shiner, monarch, lynx, piping plover and fufa redknot etc. )